



**PROJECT: 71<sup>st</sup> Classical High School Roof Re-Cover**

**ADDENDUM 01      DATE: 05-15-23**  
**BID DATE: 05-23-23 / TIME: 2:00PM**

**OWNER: Cumberland County Schools**  
**VIA: EMAIL TO ALL BIDDERS**

**ARCHITECT: THOMAS GOETZ (910-850-0460)**  
[t.goetz.architect@gmail.com](mailto:t.goetz.architect@gmail.com)

This Addendum is issued prior to receipt of the bids and shall and does hereby become a part of the drawings, specifications and project manual for the project. All principal contractors shall be responsible for seeing that their subcontractors are properly appraised of the contents of this addendum. All information in the addendum shall supersede and take precedence over any conflicting information in the original drawings, specifications and project manual.

All contractors shall acknowledge receipt of the addendum.

The following changes, additions and clarifications are made to the drawings and project manual for the above referenced project. Number of pages: 1 of clarifications

**DRAWING / SPECIFICATIONS**

**01** – Section 07530 PVC Adhered Single Ply Membrane Roofing, Part 2 Paragraph 2.1B should read: Sarnafil G410 in lieu of SikaPlan.

**02** – Section 07530 PVC Adhered Single Ply Membrane Roofing, Part 2 Paragraph 2.1B Add manufacturer Versico as an acceptable product supplier, Product: Versiflex 60 Mil PVC.

**03** – Add 2x nailers with proper anchorage at all parapet conditions where new metal coping is to be provided.

**04** – Areas designated for roof re-cover include: A , B, C, D and E as shown on A100.

**05** – Core samples are being taken and I hope to have the results for you this week.

**END OF ADDENDUM NO. 01**