



**PROJECT: Massey Hill Classical High School Roof Re-Cover**

**ADDENDUM 02    DATE: 05-18-23**  
**BID DATE: 05-23-23 / TIME: 2:00PM**

**OWNER: Cumberland County Schools**  
VIA: EMAIL TO ALL BIDDERS

**ARCHITECT: THOMAS GOETZ (910-850-0460)**  
[t.goetz.architect@gmail.com](mailto:t.goetz.architect@gmail.com)

This Addendum is issued prior to receipt of the bids and shall and does hereby become a part of the drawings, specifications and project manual for the project. All principal contractors shall be responsible for seeing that their subcontractors are properly appraised of the contents of this addendum. All information in the addendum shall supersede and take precedence over any conflicting information in the original drawings, specifications and project manual.

All contractors shall acknowledge receipt of the addendum.

The following changes, additions and clarifications are made to the drawings and project manual for the above referenced project. Number of pages: 1 of clarifications

**DRAWING / SPECIFICATIONS**

**01 - Core samples were taken on the above referenced project and are provided as follows:**

AREA "A" ----- Approximate thickness to top of deck

1 – 3"

2 – 3"

3 – 2-3/4"

4 – 3-1/2"

AREA "B" ----- Approximate thickness to top of deck

1 – 3-1/4"

2 – 3-1/2"

Although there is slope in the structure, the roof composition appears to be made up of a layering of polyiso. insulation with a cover board over which the built up is applied. Deck material is wood except at the elevator tower.

**END OF ADDENDUM NO. 02**

