



PROJECT: 71st Classical High School Roof Re-Cover

ADDENDUM 02 DATE: 05-18-23
BID DATE: 05-23-23 / TIME: 2:00PM

OWNER: Cumberland County Schools
VIA: EMAIL TO ALL BIDDERS

ARCHITECT: THOMAS GOETZ (910-850-0460)
t.goetz.architect@gmail.com

This Addendum is issued prior to receipt of the bids and shall and does hereby become a part of the drawings, specifications and project manual for the project. All principal contractors shall be responsible for seeing that their subcontractors are properly appraised of the contents of this addendum. All information in the addendum shall supersede and take precedence over any conflicting information in the original drawings, specifications and project manual.

All contractors shall acknowledge receipt of the addendum.

The following changes, additions and clarifications are made to the drawings and project manual for the above referenced project. Number of pages: 1 of clarifications

DRAWING / SPECIFICATIONS

01 – Core samples were taken on the above referenced project and are provided as follows:

AREA "A" ----- Approximate thickness to top of deck

1 – 1-1/4"

2 – 1"

3 – 1-1/4"

AREA "B" ----- Approximate thickness to top of deck

1 -1"

2 – 1"

AREA "C" ----- Approximate thickness to top of deck

1 – 1"

2 – 1-1/4"

AREA "E" ----- Approximate thickness to top of deck (this area shows tapered insulation at 1/8" per foot

1 – 1-1/4"

There is slope in the structure in areas "A" / "B" and "C". Area "E" has a taper at approximately 1/8" per foot. The roof composition in areas "A", "B", "C" appears to be made up of a cover board over which the built up is applied (no insulation) Deck material is wood in all areas except at the elevator tower.

END OF ADDENDUM NO. 02

