



LOCKLEAR, LOCKLEAR & JACOBS, PLLC

P.O. Box 3119 Pembroke, NC 28372 Phone: (910) 774-9306 Fax: (866) 649-7235

Terry Sanford High School Gym Hydronic Pipe Replacement

ADDENDA #1

Date: 5-30-23

All items on this form are considered **Addenda #1** and shall be acknowledged as considered and taken into account for bid proposes on all bid forms.

1. Any project related questions will be due by 5:00 pm on Monday May 29th, 2023. At this time, an addenda will be sent out to all contractors. Make sure to acknowledge all addenda on bid form.
2. Lifts will be required to have 5/8" plywood underneath at all times. In addition, 5/8" plywood will need to be installed on floor under the areas being worked on to prevent damage from falling or dropped items.
3. Question: Is Nupi Niron Clima pipe PP-RCT SDR 9 an approved equal to the Aquatherm blue pipe SDR 9 MF RP? Answer: Yes